

INSERT PAGES
IBC CHAPTER 19

To be inserted between pages 382 & 383.

Comm 62.1915 Column approvals. Substitute the following wording for the requirements in IBC section 1915.6.: Details of column connections and splices shall be shop-fabricated by approved methods and testing. Shop-fabricated concrete-filled pipe columns shall be inspected by a representative of the manufacturer at the plant.