



Jim Doyle, Governor
Mary P. Burke, Secretary

June 21, 2005

DUTCH HOUSING, INC.
BRADD GIGGY
1500 N DETROIT ST
PO BOX 258
LAGRANGE IN 46761

Re: Description: PREFABRICATED PLUMBING SYSTEM
Manufacturer: DUTCH HOUSING, INC.
Product Name: MODULAR HOME -PREFABRICATED PLUMBING TREE
Model Number(s): FM 21/FM 22
Product File No: 20050363

The specifications and/or plans for this plumbing product have been reviewed and determined to be in compliance with chapters Comm 82 through 84, Wisconsin Administrative Code, and Chapters 145 and 160, Wisconsin Statutes.

The Department hereby issues an approval based on the Wisconsin Statutes and the Wisconsin Administrative Code. This approval is valid until the end of June 2010.

This approval is contingent upon compliance with the following stipulation(s):

- The flowing water supply pressure at the point(s) of connection must be at least 43 psig.
- The manufacturer must keep at the manufacturing plant a set of plans and specifications bearing the department's stamp of approval. The plans and specifications must be open to inspection by an authorized representative of the department.
- The maximum water supply fixture units (wsfu) on CPVC tubing must not exceed 24 wsfu for 1-inch tubing, 13 wsfu for 3/4-inch tubing and 5 wsfu for 1/2-inch tubing.
- The maximum water supply fixture units (wsfu) on Type M copper tubing must not exceed 34.0 wsfu for 1-inch tubing, 18.0 wsfu for 3/4-inch tubing and 7.5 wsfu for 1/2-inch tubing.

A copy of the approved plans and/or specifications is enclosed.

The department is in no way endorsing this product or any advertising, and is not responsible for any situation which may result from its use.

Sincerely,

Michael J. Beckwith, CIPE
Plumbing Product Reviewer
phone: 608-266-6742
fax: 608-267-9566
e-mail: mbeckwith@commerce.state.wi.us