



**Jim Doyle, Governor**  
**Mary P. Burke, Secretary**

April 14, 2006

DUTCH HOUSING, INC.  
BRADD GIGGY  
1500 N DETROIT ST  
PO BOX 258  
LAGRANGE IN 46761

Re: Description: PREFABRICATED PLUMBING SYSTEM  
Manufacturer: DUTCH HOUSING, INC.  
Product Name: MODULAR HOME-DWV LINES  
Model Number(s): CSB 1501/CSB1502  
Product File No: 20060112

The specifications and/or plans for this plumbing product have been reviewed and determined to be in compliance with chapters Comm 82 through 84, Wisconsin Administrative Code, and Chapters 145 and 160, Wisconsin Statutes.

The Department hereby issues an approval based on the Wisconsin Statutes and the Wisconsin Administrative Code. This approval is valid until the end of April 2011.

This approval supersedes the approval issued on January 14, 2005, under product file number 20040627.

This approval is contingent upon compliance with the following stipulation(s):

- The flowing water supply pressure at the point(s) of connection must be at least 34 psig.
- The manufacturer must keep at the manufacturing plant a set of plans and specifications bearing the department's stamp of approval. The plans and specifications must be open to inspection by an authorized representative of the department.
- This plumbing product must be installed in accordance with Cardinal Industries, Inc. Plumbing Standards and Installation Procedures manual, revised 1/30/87.
- The maximum water supply fixture units (wsfu) on CPVC tubing must not exceed 24 wsfu for 1-inch tubing, 13 wsfu for 3/4-inch tubing and 5 wsfu for 1/2-inch tubing.

The department is in no way endorsing this product or any advertising, and is not responsible for any situation which may result from its use.

Sincerely,

Michael J. Beckwith, CIPE  
Plumbing Product Reviewer  
phone: 608-266-6742  
fax: 608-267-9566  
e-mail: mike.beckwith@wisconsin.gov