



Jim Doyle, Governor
Mary P. Burke, Secretary

January 10, 2007

HOMEWAY HOMES, INC.
QUALITY CONTROL
JIM STOLLER
100 HOMEWAY COURT
DEER CREEK IL 61733

HOMEWAY HOMES, INC.
PRODUCTION AND COMPLIANCE
ASSURANCE
JIM STOLLER OR BRIAN SCHIELER
100 HOMEWAY COURT
DEER CREEK IL 61733

Re: Description: PREFABRICATED PLUMBING SYSTEM
Manufacturer: HOMEWAY HOMES, INC.
Product Name: KLINGER
Model Number(s): 36'x28' CUSTOM
Product File No: 20060537

The specifications and/or plans for this plumbing product have been reviewed and determined to be in compliance with chapters Comm 82 through 84, Wisconsin Administrative Code, and Chapters 145 and 160, Wisconsin Statutes.

The Department hereby issues an approval based on the Wisconsin Statutes and the Wisconsin Administrative Code. This approval is valid until the end of January 2012.

This approval is contingent upon compliance with the following stipulation(s):

- The flowing water supply pressure at the point(s) of connection must be at least 36 psig.
- The manufacturer must keep at the manufacturing plant a set of plans and specifications bearing the department's stamp of approval. The plans and specifications must be open to inspection by an authorized representative of the department.
- The maximum water supply fixture units (wsfu) on PEX tubing must not exceed 20.5 wsfu for 1-inch tubing, 11 wsfu for 3/4-inch tubing, 8 wsfu for 5/8-inch tubing, and 4 wsfu for 1/2-inch tubing.

A copy of the approved plans and/or specifications is enclosed.

The department is in no way endorsing this product or any advertising, and is not responsible for any situation which may result from its use.

Sincerely,

Michael J. Beckwith, CIPE
Plumbing Product Reviewer
phone: 608-266-6742
fax: 608-267-9566
e-mail: mike.beckwith@wisconsin.gov