Wilbert®

Marshfield Wilbert Vault Works, Inc.
PO Box 493
Marshfield, Wisconsin 54449
T: 715.387.8628

MARSHFIELD WILBERT VAULT

SEPTIC AND HOLDING TANKS INSTALLATION INSTRUCTIONS

BEDDING REQUIREMENTS:
Tanks must be placed on soils capable of bearing the weight of tank and its contents, when full.
Soft soils or bedrock must have a minimum 3" of tamped material, sand or gravel, 100% of which passes ½ screen. The center bedding under the tank should be 1" to 2" lower than that of the perimeter bedding.

BACKFILL:
Sidewalls require backfill which 100% shall pass a 2" screen. Material to be made up of dry soil, sand or gravel. Minimum of 12" on all sides of tanks, from base to top. No parallel backfilling or compaction along length of sidewalls is permitted.

COVER MATREIAL:
Cover material shall be dry soil, sand or gravel material that has the ability of 100% to be able to pass through a 4" screen.
Standard tank design is up to 4' bury depth in heavy soils.
Soft soils contact dealer for variance.

Note:
Excavators and others are not to drive on any part of the disturbed soil and around tank.