

ALTERNATE FASTENING SCHEDULE FOR BRACED WALL PANELS⁴

**Alternatives to the Fastener Schedule Table in UDC Appendix
as referenced by SPS 321.02(1)(d)**

Item	Material	Fastener		Spacing of Fastener	
		Type Minimum	Nominal Length	Edges	Intermediate Supports
	Wood structural panel for wind bracing to wall framing				
1	5/16" to 1/2"	0.113" nail (6d common nail)	2"	6"	12"
2		0.113" deformed shank nail ¹	2" 2-3/8"	6"	12"
3		14 gage staple ²	2" 2-1/4" 2-1/2" 3"	6"	12"
4		15 gage staple ²	1-3/4" 2" 2-1/4" 2-1/2"	6"	12"
5	5/8" to 3/4"	0.131" nail (8d common nail)	2-1/2"	6"	12"
6		0.131" deformed shank nail ¹	2-3/8"	6"	12"
7		0.113" deformed shank nail ¹	2" 2-3/8"	4"	8"
8		14 gage staple ²	2" 2-1/4" 2-1/2" 3"	4"	8"
	1/2" Gypsum Wallboard panel for wind bracing to wall framing (interior) ³				
9		Type W or S screw	1 1/4"	7"	7"
10		Galvanized roofing nail	1 1/2"	7"	7"
11		16-gage galvanized staple ²	1 1/2"	7"	7"

Footnotes:

1. Clipped and notched nail heads are permitted. T-type nail heads are not permitted.
2. Staples must have minimum 7/16 inch crown widths.
3. 4' x 8' or 4' x 9' panels shall be applied vertically.
4. For further info, see ICC-ES Report # 1539 at www.icc-es.org